No.	296 Items of work	Per	Quantity	Rat
	School Main Building—contd.			Rs.
22	Tarring the woodwork inbedded in mortar ...	Lump sum		
23	Flooring with First Class Mangalore tiles 8" concrete bed with cement pointing laid diagonally.	Sqr.	13·15	
24	Flooring with Cuddapah slabs on 3" concrete with cement pointing.	„	4·01	
25	Teakwood eave board with painting 9" width and 1" thick.	R.ft.	268	
26	Cement pointing to basement ...	Sqr.	3·47	
27	Perforated brick work including plastering ...	No.	6	
28	Ornamental work around windows	Lump sum		
29	Chunam borders	Lump sum		
30	Inscription stone	Lump sum		
31	Teakwood finials	No.	5	
32	Pendents	No.	8	
33	Cutting "U" shape in stone pillars	No.	6	
34	Constructing a latrine of the open type in the north-east corner in the compound.	Lump sum		
	Compound wall.			
1	Earthwork excavation foundation	C.yd.	31	
2	Concrete for foundation	C.ft.	428	
3	Burnt brick in mortar foundation	„	465	
4	Do in clay superstructure	„	509	
5	Burnt stone slabs dressed and fixed 6" thick ...	S ft.	12	
6	Plastering with chunam	Sqr.	18 47	
7	Whitewashing as per plastering ...	„	18 47	
8	Burnt brick in chunam coping 9" studded with glass pieces over.	R.ft.	188	
9	Teakwood gate with iron wheels, etc., complete with painting complete double shutters.	Sqr.	52	

N. G. KRISHNA IYENG
Executive Engi

KOLAR DIVISION.

Notice.

The attention of the public is invited to the Notification in the *Mysore Gazette*, pages 386 and 387, dated 3rd April 1930, calling for tenders for Restoring Alahalli kere, Reg. No. 150 of Kolar Taluk.

The last date of tender is 2 P. M. of 21st April 1930.

Dated 12th April 1930.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M., on 2nd May 1930, for Constructing District Office Building at Kolar. An approximate estimate of quantities is given below. The quantities are not guaranteed. A progress of Rs. 5,000 should be given before 1st 1930 and the work must be completed by December 1930. These terms will be enforced.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar Division between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form [illegible] at which the different items specified will be executed.

for Constructing District Board Office Building at Kolar" in default of which, tenders will be rejected

5. The final acceptance of any tender will rest with the Chief Engineer of Mysore, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender the successful competitor will be required to execute the usual contract bond in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

9. The tenderers must quote specific rates for each item of work both in words and in figures.

10. The tenderers stating that the work would be executed at a certain percentage of or lower than the estimate will not be accepted.

Abstract estimate for constructing District Board's Office at Kolar.

No.	Items of work	Per	Quantity	Cost
				Rs.
1	Earthwork excavating foundation	C.yd.	303	
2	Metal concrete in chunam	C.ft.	1,484	
3	Burnt stone in chunam	,,	7,993	
4	Burnt brick in chunam	,,	8,944	
5	Arch work burnt brick in chunam	,,	159	
6	Releiving arch burnt brick in chunam	,,	496	
7	Plastering with chunam	Sqr.	125·18	
8	Pointing in chunam	,,	9·78	
9	Burnt stone slabs 6' thick dressed and fixed ...	S.ft.	2,096	
10	Cut stone pillars with base and capitals 6½' and 5/8' x 5/8'	Each	4	
11	Teakwood wrought and put up	C.ft.	41 25	
12	Rolled steel beams 15" x 5" including hoisting and painting, etc., complete.	C.wt.	16·5	
13	Rolled steel joists 6" x 3" including hoisting and painting, etc., complete.	,,	134·8	
14	Jack arch Terrace	Sqr.	28·48	
15	Roofing with First Class Mangalore tiles on teak reepers, etc., complete.	,,	7·80	
16	Ridge tile set in mortar . ..	R.ft.	26	
17	Cornice 9" thick	,,	448	
18	Ornamental teakwood eave board 9" wide	,,	138	
19	Ordinary parapet wall 3" high	,,	361	
20	Teakwood doors with pannelled shutters, etc., complete	S.ft.	411	
21	Teakwood windows with pannelled shutters outside and glazed inside with hooks, etc., complete.	,,	300	
22	Teakwood ventilaters glazed	,,	72	
23	Chunam borders over roof 9"	R.ft.	66	
24	Chocolate painting silicate 3 coats	Sqr.	18·67	
25	Wood oiling	,,	5.58	
26	Tarring.	,,	2·00	
27	Teakwood pendents	Each	4	
28	Teakwood finials	,,	2	
29	Flooring with burnt stone slabs on 8" concrete bed and cement pointing.	Sqr.	26·40	
30	Zinc rain water spouts	R ft.	224	
31	Ornamental capitals to pillars between arches and pillasters and string course.	Lump	sum	
32	White washing 2 coats			